NOTE: BEARINGS USED FOR THIS SURVEY ARE "DEED BEARINGS."

UNION PACIFIC RAILROAD

Set 5/8" I.R.

59.20'

Manhole

(S 30° 15' W) - - - 139.20'

Set R.R. Spike

Load Pol

Pwr Pole

Top Existing Fill

80.00'

S 61° 06' E 65.50'

Set 5/8" I.R.

R.R. R/W ?

28.2'

23.2'

3.5'

12" Conc. Culvert

65.50'

Set R.R. Spike

80.00'

N 30° 15' E

Set R.R. Spike

(N 61° 06' W - - - 135.50') DEED

70.00'

T.L. 1900

POST OFFICE

1392.69' Radius

N 28° 25' 30" E CH=23.10' L=23.10'

I.T. 0.5'

FD AXEL Set 5/8" I.R. 3'x3' Telephone Booth

40'

Set Nail

187'

N 28° 58' E (N 28° 53' E) Deed

T.L. 1500

T.L. 1400

(S 43° 15' E - - - 145.92') Deed

S 43° 15' 15" E - - - 146.05' Meas.

Fd. I.P. 0.15' So.

43.77'

12'

Fd. I.P. Buried 0.5'

FIRE STATION

54'

40'

30.3'

40.9'

0° 55'

N 29° 53' E - - - 93.93'

Existing Curb

40'

30.2'

60° 47'

(N 28° 53' E) DEED

160.82'

SET CONC. NAIL - BACK SIDEWALK

TAX LOT 1300

Fd. I.P.

134.87'

Fd. I.R.

64.78'

Fd. 2" I.P.

80'

40'

28'

℄ OLD COLUMBIA (N 28° 53' E) DEED RIVER HIGHWAY

90°

CASCADE LOCKS

(118.43') Deed

3664.87' W. and 1476.76' S. of the E 1/4 Cor. Sec. 12

(32.13') (S 61° 06' E)

℄ REGULATOR ST.

S 89° 20' E - - - 371.90'

60'

N.W. Cor. Block 4 Not Found.

(5th.)

(264.00')

℄ VENTURE ST. (14th.)

(260.00')

S 00° 40' W - - 259.98'

Fd I.P.

℄ MOODY AVENUE

Fd Axel

90°

FILED

APR 29 1983

COUNTY SURVEYOR

Richard G. Arnold

DEPUTY

REGISTERED PROFESSIONAL LAND SURVEYOR

David L. Tuttle

OREGON DAVID L. TUTTLE JULY 12, 1968 822

Date	No.	Revisions	By	App.

SURVEY

TAX LOT 1300

FOR CITY OF CASCADE LOCKS

IN THE S.W. 1/4 OF SEC. 12, T. 2N. R. 7E. W.M.

Hood River County, Oregon.

Design	TENNESON ENGINEERING CORP. Consulting Engineers 409 Lincoln Street The Dalles Oregon		Scale 1" = 20'
Survey D.L.T.			Date 3-4-83
Drawn S.D.H.	Checked	Approved	Work Order No. 6385
			Sheet 1 of 1

Drafting Specialties

93021

#83021